



**CITY OF PALM DESERT
CALIFORNIA**

ADDENDUM NO. 3

LINE 4 DRAINAGE PROJECT

**PROJECT NO. 522-16
CONTRACT NO. C35310A**

ISSUED May 24, 2019

A handwritten signature in blue ink, appearing to read 'Bo Chen', is written over a horizontal line.

**BO CHEN, P.E.
CITY ENGINEER**

**IMPORTANT NOTE: RECEIPT OF THIS ADDENDUM MUST BE
ACKNOWLEDGED IN CONTRACTOR'S PROPOSAL**

This addendum provides answers to questions regarding the contract documents.

1. May native material be used for pipe bedding?

Answer: Yes.

2. Is slurry backfill required any place other than Line E-1?

Answer: Slurry backfill is also required in the 4' deep trench for the traffic communication conduit as described in Addendum No 2.

3. Is cold mix acceptable over laterals until permanent AC is placed?

Answer: Cold mix may be used for temporary paving. The temporary paving must be a minimum of 3" thick in accordance with the encroachment permit.

4. Will work hours be restricted on Country Club Drive?

Answer: Work hours on Country Club Drive will be from 5:30 a.m. to 7:00 p.m. The City reserves the right to extend work hours for the benefit of the project.

5. Would the City allow the contractor to close westbound Country Club Drive to through traffic?

Answer: The City will consider allowing the contractor to detour westbound traffic during work hours. The street must be reopened every day following construction activities.